

CAMPSFIELD ROAD, HARINGEY

■ Regeneration, Flat to Pitch Project



Client: Homes for Haringey
Contractor: Infallible Systems Ltd
Completed: March 2010

Size: 2500m²
System Used: Langley Flat to Pitch Roofing System

Campsfield Road

Langley had worked closely with Wates Living Space and approved contractor Infallible Systems Ltd to project manage this large programme of works for Homes for Haringey.

This has provided the client with an exceptional Flat to Pitched roof conversion, as shown in this fine example of estate regeneration.

As well as dealing with the design of the roof conversion and associated structural engineering, Langley also managed the Planning and Building control requirements on this project.

The roof system consists of a bespoke Langley Flat to Pitched roofing system measuring 2500m² over four blocks (Campsfield House, Gillett House, Myddelton House and Honeymead House).

Langley had to overcome certain design issues on this project which included the client's requirement for full new roof void access. This required the cutting of new access hatches and in some cases, the introduction of a dormer feature to some of the hip ends.

Main System Products:

Langley Flat to Pitch Frame System
Langley Flat to Pitch Soffit/Fascia/Gutter System
Langley Villatile Tile Panels



CASE STUDY

Langley Waterproofing Systems Ltd

Bishop Crewe House, North Street, Daventry, Northants, NN11 4GH
Tel: 01327 704778 Fax: 01327 704845 Sales: 01327 708990 Website: www.langley.co.uk